

To: 1 040753 5-4
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,479-0000
Approx. C
NW NE, SEC. 30, T 23 S, R 12 W/EX
4726 feet from S section line
1874 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5023
Operator: Kansas Petroleum, Inc.
Name &
Address 225 N. Market, Ste. 310
Wichita, KS 67202

Lease Name Meis Well # 1
County Stafford
Well Total Depth 3920 127.40 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 296

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kansas Petroleum, Inc. License Number 5023
Address 225 N. Market, Ste. 310, Wichita, KS 67202

Company to plug at: Hour: 8:30 a.m. Day: 4 Month: 5 Year: 1993

Plugging proposal received from Bill Luck
(company name) Kansas Petroleum, Inc. (phone) 316-792-2051

were 5 1/2" at 3920' w/250 sx cement, PBD 3672', Perfs at 3470-74, 3556-60, 3622-28'
5 1/2" casing had been squeezed w/cement. from 2575' w/250 sx out at 2575' and 100 sx down 5 1/2" X
8 5/8" annulus to fill up.

Pump down 5 1/2" casing with 500 lbs. hulls in with first of 285 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9 a.m. Day: 4 Month: 5 Year: 1993

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 500 lbs. hulls in with first
part of 285 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Rec'd 5-21-93

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (did) ~~not~~ observe this plugging.

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOLVED
DATE 5-17-93
WV. NO. 37720
5-4