

To: 1 120631
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS. 67202

9-24 208
API NUMBER 15- D-18,601 15-185-01374-0001 R
SEC. 34 T 23 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6981
Operator: Gas Marketing, Inc.
Name & Address: P.O. Box 159
Stafford, KS 67578

4290 feet from S section line
4290 feet from E section line
Lease Name Heyen Well # 1
County Stafford 146.34
Well Total Depth 4503 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635
Address Great Bend, KS

Company to plug at: Hour: 9 a.m. Day: 24 Month: 9 Year: 19 91

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 3920', PBSD 2600', Open hole 3920-4503',
1st plug set packer at 2500' and squeeze 100 sx cement in 5 1/2" casing,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 24 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set packer at 2500' and squeezed 100 sx cement in 5 1/2"

casing, top of cement @ 2591',
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-100 psi and shut in 50 psi.

RECEIVED
STATE CORPORATION COMMISSION
10-1-91
OCT 01 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1740' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOLCED

Observe this plugging.

DATE 10-18-91

Signed Duane Rankin (TECHNICIAN)

INV. NO. 33395