

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20217-00-00
Spot: CS2 Sec/Twnshp/Rge: 16-21S-32W
1170 feet from S Section Line, 2640 feet from E Section Line
Lease/Unit Name: RAGSDALE Well Number: 1
County: FINNEY Total Vertical Depth: 2723 feet

Operator License No.: 31566 Conductor Pipe: Size _____ feet:
Op Name: BENCHMARK OIL & GAS CORPORATION Surface Casing: Size 8.625 feet: 372 CMT N/A
Address: 1515 ARAPAHOE ST STE 580 Production: Size 4.5 feet: 2710 CMT N/A
DENVER, CO 80202 Liner: Size _____ feet: _____ 88.50

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/27/2000 10:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: ROLAND NYP Company: BENCHMARK OIL & GAS Phone: (303) 595-9251

Proposed Plugging Method: PUMP 50 SX CMT 300-400# HULLS GEL WATER TO 1350'. PERFORATE AND PUMP CASING COLUME PLUS 80 SX CMT. THEN PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/27/2000 4:00 PM

KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 2679-89'. CASING LEAK @ APPROXIMATELY 1500'. L & K WIRELINE PERFORATED AT 1350'. KEY WELL SERVICE RAN TUBING TO 2656'. ALLIED PUMPED DOWN 1 1/2" TUBING 200# HULLS, PULLED TUBING UP TO 2390' AND PUMPED 20 SX CMT WITH 100# HULLS MIXED IN. PULLED UP TO 1358' AND PUMPED 65 SX CMT AND CIRCUALTED TO SURFACE. PULLED TUBING OUT OF HOLE & PUMPED DOWN 4 1/2" CASING WITH 80 SX CMT. MAXIMUM PRESSURE 1300#. WELL ON VACUUM SHUT IN. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 175 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN AT 50#. TOPPED OFF 4 1/2" WITH 10 SX CMT. STAYED AT SURFACE.

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

JAN 02 2001

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Kevin D Strube
(TECHNICIAN)

INVOICED

DATE 1/3/01

DEC 28 2000

INV. NO. 2001061221

Form CP-2/3