

To: 1-120393
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-3 15-185-21869-0000 63
API NUMBER 15- NA
App. 100 S of
C NW NW NE, SEC. 15, T 22 S, R 12 W/E
4850 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3243
Operator: Commonwealth Petroleum Corp.
Name & Address: P.O. Box 2458
Hutchinson, KS 67504

Lease Name Seifkes "A" Well # 1
County Stafford 122.53
Well Total Depth 3770 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 3 Month: 4 Year: 1990

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3769' Open hole Elevation 1853' GL
1st plug sand back to 3700' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 3 Month: 4 Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3700' and dumped 5 sx cement
on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 sx cement, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-800 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2440' of 5 1/2" casing.

INVOICED

DATE APR 13 1990

INV. NO. 27839

If additional description is necessary, use BACK of this form.)

I (did / XXXXXXX) observe this plugging. 4-6-90

Signed [Signature] (TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KANSAS