

To: 1 120567
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-9 15.185.01306-0001
API NUMBER 15- Drilled 6/44 380
SW SE SW, SEC. 15, T. 22 S, R. 12 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5472

Operator: Hoppe Oil & Gas Company, Inc.
Name & Address 212 N. Market, Suite 315
Wichita, KS 67202

330 feet from S section line

3630 feet from E section line

Lease Name Fruehauf Well # 1

County Stafford 116.67

Well Total Depth 3590 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 378

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 6/9 Month: 5 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 3590', Perfs at 3436-3440'
1st plug sand back to 3385' and dump 4 sx cement on top of sand through bailer,
2nd plug pump in 10 3/4" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 150 lbs. hulls and 175 sx cement.

Plugging Proposal Received by Duane Rankin

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 6/9 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3385' and dumped 4 sx cement
on top of sand through bailer,

2nd plug pumped into 10 3/4" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 150 lbs. hulls and 175 sx cement.

Pumping pressure 0-1000 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION

5-13-91
MAY 13 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1300' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 5-22-91

INV. NO. 31868

Signed Duane Rankin
(TECHNICIAN)