

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-13253-00-00
Spot: S2N2NE Sec/Twnshp/Rge: 15-22S-12W
4290 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: SIEFKES Well Number: 1
County: STAFFORD Total Vertical Depth: 3772 feet

Operator License No.: 3182
Op Name: N P F ENERGY CORPORATION
Address: PO BOX 3827
TUSTIN, CA 92781

Conductor Pipe: Size feet: 8/22.59
Surface Casing: Size 8.625 feet: 235
Production: Size 5.5 feet: 3657 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/19/2002 9:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3400' & 5 SX CMT. SPOT 10 SX GEL & 50 SX CMT AT 650'. SPOT 50 SX CMT AT 400'. SPOT 10 SX CMT AT 40'.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/19/2002 11:10 AM

KCC Agent: RICHARD LACEY

Actual Plugging Report:


PBTD 3604'. PERFS AT 3550'. SANDED TO 3400' & 5 SX CMT. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 650' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
JAN 16 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2618' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 1-17-03

INV. NO. 2003061086

Form CR-2/3