

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-20217-00-02  
Spot: SENWNW Sec/Twnshp/Rge: 15-22S-12W  
4290 feet from S Section Line, 4360 feet from E Section Line  
Lease/Unit Name: CURTIS Well Number: 1-V  
County: STAFFORD Total Vertical Depth: 3665 feet

Operator License No.: 5047  
Op Name: RUPE OIL COMPANY, INC.  
Address: PO BOX 783010 111 WHITTIER #1000  
WICHITA, KS 67278

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 251 WITH 275 SX CMT  
Production: Size 5.5 feet: 3656 WITH 150 SX CMT  
Liner: Size feet: \$ 119.11

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/12/2001 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND TO 3200' & 5 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/12/2001 11:40 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE 3665-3656'. SAND TO 3200' AND 5 SX CMT WITH BAILER. PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT. MAXIMUM PRESSURE 500#. INITIAL SHUT IN PRESSURE 300#.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 19 2001  
CONSERVATION DIVISION

INVOICED  
DATE 6-19-01  
NO. 2001061963

Remarks: USED 60/4 POZMIX 6% GEL BY ALLIED. RECOVERED 2610' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

JUN 15 2001

*MP*

*[Signature]*  
Form SP 2/3