

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20287-00-00  
Spot: CNW Sec/Twnshp/Rge: 18-22S-31W  
1320 feet from N Section Line, 1284 feet from W Section Line  
Lease/Unit Name: JOYCE Well Number: 1  
County: FINNEY Total Vertical Depth: 2740 feet

Operator License No.: 5317  
Op Name: CONTINENTAL ENERGY  
Address: PO BOX 918  
GARDEN CITY, KS 67846

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 7 feet: 350 WITH 200 SX CMT  
Production: Size 4.5 feet: 2759 WITH 250 SX CMT  
Liner: Size \_\_\_\_\_ feet: \$89.05

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/17/2001 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: EUGEN SALOGA Company: CONTINENTAL ENERGY Phone: (316) 276-8710

Proposed Plugging Method: PERFORATE AT 1350'. RUN TUBING TO 2600' PUMP 70 SX CMT WITH 300# HULLS. PULL TUBING TO 1500' CIRCULATE CMT TO SURFACE. PULL TUBING OUT OF HOLE & PUMP 80 SX CMT OVER CASING VOLUME AND IF IT DOES NOT CIRCULATE THEN PUMP 200 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/17/2001 1:15 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 2682-90, 2709-19'. PERFORATED AT 1350'. RAN TUBING IN HOLE TO 2600'. PUMPED 70 SX CMT WITH 300# HULLS MIXED IN. PULLED TUBING TO 1500' CIRCULATED CMT TO SURFACE WITH 100 SX CMT. PULLED TUBING OUT OF HOLE. PUMP DOWN 4 1/2" CASING SQUEEZED OUT 10 SX CMT. MAXIMUM PRESSURE 1300#. SHUT IN AT 1300#. PUMPED DOWN 7" X 4 1/2" ANNULUS 30 SX CMT. MAXIMUM PRESSURE 700#. SHUT IN AT 300#.

RECEIVED  
AUG 24 2001  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Kevin D Strube  
(TECHNICIAN)

INVOICED AUG 20 2001  
DATE 8-27-01  
INV. NO. 2002060281

CP-2/3