

To: 1 052086  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 185-20,074-0000  
C NW , SEC. 24 , T 22 S, R 12 W/EX  
3960 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30729  
Operator: Gabel, Craig  
Name  
Address 1611 S. Emporia  
Wichita, KS 67211

Lease Name Heyen D Well # 1  
County Stafford 118.62  
Well Total Depth 3650 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 284

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated

Plugging Contractor D.S. & W. Well Servicing, Inc. License Number 6901  
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 9 a.m. Day: 21 Month: 11 Year: 19 96

Plugging proposal received from Kent Strube  
(company name) D.S. & W. Well Servicing, Inc. (phone) 316-587-3361

Work: 5 1/2" at 3646' w/125 sx cement, Open hole 3646-50'  
1st plug sand back to 3600' and dump .5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 125 sx cement.

11-23-96

Plugging Proposal Received by Bill Johnson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:11 a.m. Day: 21 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1657.1' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (and/or authorized) observe this plugging.

Signed Richard W. Lacey  
(TECHNICIAN)

INVOICED  
DATE NOV 26 1996  
INV. NO. 47054