

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22327-00-00
Spot: CNESENW Sec/Twnshp/Rge: 24-22S-12W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: HEYEN A Well Number: 2
County: STAFFORD Total Vertical Depth: 3648 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B WEST 10TH STREET
GREAT BEND, KS 67530

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 262 WITH 262 SX CMT
Production: Size 5.5 feet: 3646 WITH 175 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/21/2001 11:40 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND BACK TO 3600' & 5 SX CMT. 1ST PLUG AT 660' WITH 50 SX CMT. 2ND PLUG AT 290' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

118.56

Plugging Proposal Received By: STEVE PFEIFER
Date/Time Plugging Completed: 03/21/2001 1:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

OPEN HOLE. SANDED TO 3600' WITH 5 SX CMT. LOAD HOLE WITH GEL. 1ST PLUG AT 671' WITH 50 SX CMT. 2ND PLUG AT 299' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

INVOICED
DATE 4-5-01
INV. NO. 2001061581

RECEIVED
STATE CORPORATION COMMISSION
APR -5 2001
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2636' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Michael Maier
(TECHNICIAN)

MAR 22 2001

Form CP-2/3