

To: 1 120601
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
203 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-31
API NUMBER 15-185-21,699-0000 355 R
NW NE SE, SEC. 10, T 21 S, R 13 W/EX
2310 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039
Operator: L.D. Drilling, Inc.
Name & Address: RR 1, Box 183 B
Great Bend, KS 67530

Lease Name Rothgarm Well # 1
County Stafford 115.11
Well Total Depth 3542 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 289

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 31 Month: 7 Year: 19 91

Plugging proposal received from Vernon Duntz
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3541' w/150 sx cement, PBTB 3477', Perfs at 3390-96, 3336-40'
1st plug sand back to 3280' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Plugging Proposal Received by Glenn Barlow AUG 07 1991
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Wichita, Kansas

Operations Completed: Hour: 1:45 p.m. Day: 31 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3280' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped in 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement. Pumping pressure 0-800 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
I (and/or my representative) observe this plugging.

DATE 8-16-91
INV. NO. 32744

Signed *Deane Rankin*
(TECHNICIAN)