

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-10579-00-00
Spot: CNENENW Sec/Twnshp/Rge: 10-21S-13W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: SIMPSON E Well Number: 1
County: STAFFORD Total Vertical Depth: 3585 feet

Operator License No.: 5310
Op Name: FOUR-WAY OPERATING, INC.
Address: PO BOX 698
GREAT BEND, KS 67530

Conductor Pipe: Size feet: 3 1/2
Surface Casing: Size 8.625 feet: 257 WITH 225 SX CMT
Production: Size 4.5 feet: 3580 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/02/2002 11:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: JIM ROCKHOLD Company: FOUR-WAY OPERATING Phone: (620) 792-2506

Proposed Plugging Method: RUN TUBING TO 2865' AND CIRCULATE TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/02/2002 1:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 2548'. PERFS AT 3273-76, 3291-93, 3315-17, 3323-26, 3342-43, 3394-3406'. SQUEEZED AT 2950' WITH 100 SX CMT. SQUEEZED TWICE AT 352' WITH A TOTAL OF 250 SX CMT. 1ST PLUG RAN TUBING TUBING TO 2865' AND PUMP 10 SX GEL WITH 500# HULLS MIXED WITH GEL & 30 SX CMT. 2ND PLUG PULL TUBING TO 700' AND CIRCULATE HOLE WITH 75 SX CMT. BACKSIDE WAS FULL.

RECEIVED

AUG 07 2002 8-7-02

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed

Steve Durrant

(TECHNICIAN)

AUG 05 2002

INVOICED

DATE 8-7-02

INV. NO. 2003060175