

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12843-00-00
Spot: CNESE Sec/Twnshp/Rge: 10-21S-13W
2307 feet from S Section Line, 420 feet from E Section Line
Lease/Unit Name: ROTHGARN Well Number: 2
County: STAFFORD Total Vertical Depth: 3536 feet

Operator License No.: 31647

Production Casing Size: 5.5 feet: 3532

\$114.92

Op Name: CHURCHHILL, KIM DBA K.C. OPERATIONS

Surface Casing Size: 8.625 feet: 260

Address: 534 S E 70 AVE.
ELLINWOOD, KS 67526

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/13/2003 8:00 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: KIM CHURCHILL

Company: KC OPERATIONS

Phone:

Proposed Plugging Method: PROPOSED PLUGGING SAME AS ACTUAL PLUGGING REPORT.

RECEIVED

MAR 03 2003

KCC WICHITA

Plugging Proposal Received By: STEVE DURRANT

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 02/13/2003 11:45 AM

KCC Agent: RICHARD LACEY


Actual Plugging Report:

ATTEMPTED TO PULL CASING, NO STRETCH, SQUEEZED IN. SANDED BOTTOM TO 3147'. PLACED 5 SX CMT ON TOP OF SAND. PERFORATED 5 1/2" AT 1600' & 700'. RAN TUBING TO 1600'. SPOTTED 50 SX COMMON CMT 4% CC. TAGGED PLUG AT 1298'. RAN TUBING TO 700'. PUMPED 70 SX CMT & CIRCULATED CMT UP 5 1/2". SHUT IN 5 1/2" & PUMPED 145 SX CMT & CIRCULATED CMT UP 8 5/8" X 5 1/2" ANNULUS. PULLED TUBING & TOPPED OFF HOLE WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 3-3-03

NO. 2003061263