

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22787-00-00
Spot: SESENW Sec/Twnshp/Rge: 9-22S-12W
2970 feet from S Section Line, 3120 feet from E Section Line
Lease/Unit Name: TEICHMANN Well Number: 1
County: STAFFORD Total Vertical Depth: 3825 feet

Operator License No.: 4732

Conductor Pipe: Size feet:

Op Name: MOORE, CLAY

Surface Casing: Size 8.625 feet: 264 WITH 160 SX CMT

Address: 6440 N. CENTRAL EXPWY. 620 UNIVER
DALLAS, TX 75206

Production: Size 5.5 feet: 3818 WITH 150 SX CMT

Liner: Size feet: 8124.31

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/11/2001 10:00 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND TO 3280' & 5 SX CMT. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 07/11/2001 12:30 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3744'. PERFS AT 3338-42, 3446-48, 3461-67, 3481-84, 3504-05'. SANDED TO 3280' & 5 SX CMT. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

INVOICED

DATE 7-6-01

INV. NO. 2002060068

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2028' OF 5 1/2" CASING.

Plugged through: CSG

District: 01 RECEIVED
KANSAS CORPORATION COMMISSION

Signed

Richard W. Lacey

(TECHNICIAN)

JUL 16 2001

7-16-01

JUL 12 2001

CONSERVATION DIVISION

Form CP-2/3

NP