

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12316-00-01-02
Spot: NESESE Sec/Twnshp/Rge: 1-22S-14W
990 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: WILSON Well Number: 3
County: STAFFORD Total Vertical Depth: 4032 feet

Operator License No.: 3942
Op Name: BIG "O"
Address: 2820 PASEO DRIVE
GREAT BEND, KS 67530

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 368 WITH 175 SX CMT
Production: Size 5.5 feet: 3866 WITH 50 SX CMT
Liner: Size feet:

\$131.04

Well Type: SWD UIC Docket No: D01607.0 Date/Time to Plug: 09/10/2001 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ORVILLE MONROE Company: BIG "O" Phone: (316) 792-2868

Proposed Plugging Method: RUN TUBING TO 810' AND CIRCULATE CMT TO SURFACE. PRESSURE CHECK 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/10/2001 11:50 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE 3866-4032'. 5 1/2" SQUEEZED 2750' WITH 50 SX CMT, 1500' WITH 15 SX CMT, 730' WITH 250 SX CMT. PRIOR TO 03/06/01 WELL WAS SQUEEZED AT 701-800 WITH 300 SX CMT. ON 03/06/01 ATTEMPTED TO CMT IN TUBING STRING WITH 300 SX CMT. TUBING PARTED DUMPING THE 300 SX CMT DOWN HOLE. TAGGED CMT AT 2207' ON 03/06/01. PUMPED 60 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. MAXIMUM PRESSURE 550#. SHUT IN PRESSURE 350#. RAN TUBING DOWN 5 1/2" TO 810'. CIRCULATED CMT DOWN TUBING AND UP 5 1/2" TO SURFACE WITH 80 SX CMT. PULLED TUBING AND TOPPED OFF 5 1/2" WITH 5 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)



RECEIVED INVOICE

SEP 17 2001 DATE 9-18-01 SEP 14 2001

KCC WICHITA W.V. NO. 2002060483

