

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-30294-00-00
Spot: SESENWSW Sec/Twnshp/Rge: 3-22S-12W
1600 feet from S Section Line, 1100 feet from W Section Line
Lease/Unit Name: MAX SITTNER Well Number: 6
County: STAFFORD Total Vertical Depth: 3724 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

Conductor Pipe: Size feet: \$121.03
Surface Casing: Size 8.625 feet: 649 WITH 500 SX CMT
Production: Size 5.5 feet: 3723 WITH 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/28/2001 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SANDED BACK TO 3500' & 5 SX CMT. 1ST PLUG AT 670' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/28/2001 12:45 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PERFS AT 3632'. SAND BACK TO 3500' & DUMP 5 SX CMT ON TOP WITH BAILER. 1ST PLUG SPOT 10 SX GEL & 50 SX CMT AT 670'. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. CMT TO SURFACE. GOOD CIRCULATION THROUGHOUT JOB.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

[Signature]
(TECHNICIAN)

RECEIVED

OCT 05 2001

KCC WICHITA

INVOICED

OCT 02 2001

DATE 10-05-01

INV. NO. 2002060738

Form 20-313