

To: 1 120536
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

-API NUMBER 15- Drilled 3/9/40

NE NE SE, SEC. 3, T 22 S, R 12 W/E

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3613

Lease Name Siefkes "C" Well # 7

Operator: Hallwood Petroleum, Inc.

County Stafford 117.22

Name & Address 4582 S. Ulster St. Pkwy., Ste. 1700
Denver, CO 80237

Well Total Depth 3607 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hallwood Petroleum, Inc. License Number 3613

Address 4582 S. Ulster St. Pkwy., Ste. 1700, Denver, CO 80237

Company to plug at: Hour: 1 p.m. Day: 1 Month: 3 Year: 19 91

Plugging proposal received from George Hutton

(company name) Hallwood Petroleum, Inc. (phone) 316-792-2756

were: 5 1/2" at 3601' w/75 sx cement, Open hole, Casing squeezed at 2620' w/100 sx cement
1st plug pump in 5 1/2" casing with 300 lbs. hulls, 25 sx cement, 20 sx gel, and push plug
to 700',

2nd plug perforate casing at the anhydrite and circulate cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:45 p.m. Day: 1 Month: 3 Year: 1991

ACTUAL PLUGGING REPORT 1st plug pumped into 5 1/2" casing with 250 lbs. hulls and mixed
50 lbs. hulls with 25 sx cement, followed by a 68 bbl. slurry of gel. Released plug and
pushed plug with water to 700',

Kelso Casing Pulling shot casing at 679' and circulated cement to the bottom of the
cellar with 210 sx cement. Shut in annulus and squeezed with 15 sx cement. Shut in with
250#.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered no casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-11-91

MAR - 6 1991

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 31107

MAY 03 1991

3-6-91