

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21058-00-00  
Spot: CE2SWNE Sec/Twnshp/Rge: 3-22S-12W  
~~300~~ feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: SIEFKES A Well Number: 10  
County: STAFFORD Total Vertical Depth: 3602 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: RR 1 BOX 183B WEST 10TH STREET  
GREAT BEND, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet: 117.07  
Surface Casing: Size 8.625 feet: 639 WITH 375 SX CMT  
Production: Size 6 feet: 3597  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/19/2001 11:15 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: PUMP 400# HULLS - 50 SX CMT - 18 SX GEL - 150 SX CMT DOWN 6". PRESSURE CHECK. PUMP 75 SX CMT DOWN BACKSIDE. PRESSURE CHECK

Plugging Proposal Received By: RICHARD LACEY  
Date/Time Plugging Completed: 12/19/2001 1:10 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: RICHARD LACEY

Actual Plugging Report:


PERFS AT 3597-3602'. PUMP 400# HULLS - 50 SX CMT - 14 SX GEL - 175 SX CMT DOWN 6" CASING. MAXIMUM PRESSURE 500#. SHUT IN AT 150#. PUMPED 75 SX DOWN 8 5/8" X 6" ANNULUS. MAXIMUM PRESSURE 500#. SHUT IN AT 400#.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)



RECEIVED NVOICED DEC 26 2001

Form CP-2/3

DEC 31 2001 DATE 01-02-02  
WICHITA NO 2002061114

