

1052417

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-12,602-0000
SW NE NW SEC. 3, T 22 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME SIEFKES B WELL # 11

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD

OPERATOR LICENSE # 6039 8/16 WELL TOTAL DEPTH 3612 117.39 FEET

OPERATOR: L.D. DRILLING, INC. PRODUCTION CSG: SIZE 5 1/2" @ 3608' WITH SX

NAME AND RR 1, BOX 183B SURFACE CASING: SIZE 8 5/8" @ 645' WITH SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING COMPANY LICENSE NUMBER NA

ADDRESS PO BOX 31 RUSSELL, KS 67665-0031

COMPANY TO PLUG AT: HOUR: 3:30 PM DAY: 16 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) ALLIED CEMENTING (PHONE) 785-483-2627

WERE: OPEN HOLE AT 3608-3612. WELL SQUEEZED IN AT UNKNOWN DEPTH. CEMENT IS TO SURFACE.

PUMPED DOWN 5 1/2" CASING WITH 200# HULLS- 25 SX CEMENT WITH 100# HULLS MIXED IN 26 SX GEL -

50 SX CEMENT. MAXIMUM PRESSURE 900 PSIG. SHUT IN PRESSURE 200 PSIG.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:40 PM DAY: 16 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT

PUMPED DOWN 5 1/2" CASING WITH 200# HULLS - 25 SX CEMENT WITH 100# HULLS MIXED IN 26 SX GEL -

50 SX CEMENT. MAXIMUM PRESSURE 900 PSIG. SHUT IN WITH 200 PSIG.

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 2000

REMARKS: USED 65/35 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID) OBSERVE THIS PLUGGING

INVOICED

SIGNED

Richard W. Lacey
(TECHNICIAN)

FORM CP-2/3

DATE 8/24/00

INV. NO. 2001060518

[Handwritten signature]