

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21059-00-00
Spot: CN2N2NW Sec/Twnshp/Rge: 3-22S-12W
330 feet from N Section Line, 1320 feet from W Section Line
Lease/Unit Name: SIEFKES B Well Number: 13
County: STAFFORD Total Vertical Depth: 3700 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B WEST 10TH STREET
GREAT BEND, KS 67530

Conductor Pipe: Size feet: 5 1/2
Surface Casing: Size 8.625 feet: 652 WITH 425 SX CMT
Production: Size 5.5 feet: 3698 WITH 210 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/19/2001 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3640' & 5 SX CMT. 1ST PLUG AT 680' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/19/2001 11:10 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3698-3700'. SAND TO 3640' & 5 SX CMT. 1ST PLUG AT 680' WITH 400# HULLS - 31 SX GEL - 50 SX CMT. HAD TO PUMP 31 SX GEL TO BREAK CIRCULATION. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2214' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

DEC 31 2001

INVOICED

DEC 26 2001

REC WICHITA

DATE 01-02-02

INV. NO. 2002061114



Form CP-2/3