


 KANSAS  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
 Assitant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 6 1967  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

Operator's Full Name Theodore Gore

Complete Address: 650 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Denker Well No. # 1

Location W/2 SE SE Sec. 9 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3672'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:30PM Day 2nd Month Jan. Year 1967

The Above well was plugged as follows:

338' of 8 5/8" surface pipe, cement circulated. 3669' of 5 1/2" long string,  
cemented with 150 sacks. Top perforation 3303'. Plug was pushed to 3300',  
50' of sand, and bottom was cemented with 5 sacks, through the dump bailer.  
2400' of 5 1/2" long string was recovered from the hole. Hole was squeezed.  
10 sacks of Gel-Mud and 80 sacks of cement was pumped into the surface pipe,  
through an 8 5/8" swage, to a pressure of 200 lbs. A wiping plug was run  
between th Gel-Mud and the cement.

This cementing was done by Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 1/6/67

INV. NO. 4566-W