

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1967

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Theodore Gore

Complete Address: 650 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Denker Well No. # 3

Location E/2 SW SE Sec. 9 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3686'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 1:45PM Day 2nd Month Jan. Year 1967

The Above well was plugged as follows:

340' of 8 5/8" surface pipe, cement circulated. 3685' of 5 1/2" long string,
cemented with 100 sacks. This is an open hole. Bottom of the hole was sanded
to 3675', and cemented with 5 sacks, through the dump bailer. 2595' of 5 1/2"
long string was recovered from the hole. Hole was squeezed. 10 sacks of Gel-
mud and 80 sacks of cement was pumped into the surface pipe, through an 8 5/8"
swage, to a pressure of 200 lbs. A wiping plug was run between the Gel-Mud,
and the cement.

This cementing was done by Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 1/6/67

INV. NO. 4568-W