

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 17 1965

3-17-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Alpine Oil & Royalty Company, Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name Karl Teichmann Well No. # 1

Location NE SW SW Sec. 9 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3688'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gabbert-Jones Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 12:30AM Day 16th Month March Year 1965

The Above well was plugged as follows:

298' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fluid
level in the hole was at 175'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 275', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICE
DATE 3/17/65
INV. NO. 836-w

Signed: Archie Elving
Well Plugging Supervisor