

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 79-38

LOCATION NW NW SW

SEC. 9 TWP. 22 RGE. 12

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Teichman

Operator Bishop Oil Co Address 516 Brown Bldg Wichita,

Field \_\_\_\_\_ County Stafford

Total Depth 3700 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 294' circulated with cement - 5 1/2" at 3691 with  
125 sax cement behind.

Filled with chat to 3690', set 5 sax cement with dump  
bailer, pulled 2850' 5 1/2", filled hole with mud to 250',  
set rock and 15 sax cement, filled with mud to 35', set  
rock and 10 sax cement to bottom cellar.

**PLUGGING**  
FILE SEC 9 TWP 22 R 12  
BOOK PAGE 79 LINE 38

*Edson Teets* 5-15-51  
District Conservation Agent  
**RECEIVED**  
Date 5-10-51 STATE CORPORATION COMMISSION

MAY 15 1951  
CONSERVATION DIVISION  
Wichita, Kansas