

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasIntent to Drill, filed
February 14, 1967.RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1967

2-27-67
CONSERVATION DIVISION
WICHITA, KANSASOperator's Full Name Aylward Drilling CompanyComplete Address: 909 First National Bank Bldg., Wichita, KansasLease Name Teichmann Well No. # 1Location S/2 S/2 NW Sec. 9 Twp. 22 Rge. 12 (E) (W) WCounty Stafford County Total Depth 3687'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Flugging Contractor: Gabbert-Jones, Inc.Address: 830 Sutton Place, Wichita, Kansas License No. Operation Completed: Hour 6:15AM Day 23rd Month Feb. Year 1967

The Above well was plugged as follows:

285' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid level in the hole was at 245', 1st cementing plug, bridged with 1/2 sack of hulls on fluid at 245', and cemented with 25 sacks. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 2/27/67INV. NO. 4825-W