

15-185-12316-0001

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION <sup>NE</sup> SE-SE/4

SEC. 1 TWP. 22 RGE. 14-W

Deep Salt Water Disposal  
Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3 Lease Wilson

Operator Mr. Thos. H. Allan Address #921 N. N. Bank Bldg. Wichita, Kans.

Field \_\_\_\_\_ County Stafford

Total Depth 4026 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 365 ft. Circulated with cement  
5 1/2" casing set at 3855 ft. Tools lost in hole at 3826 ft  
Set Plug x 4 sacks of cement on top of Tools at 3826 ft  
5 1/2" casing parted at at 1288 ft & Pulled out. Set  
Block Bricks & 8 sacks of cement at 1165 ft. Mud to  
345 ft. B. Bricks x 20 sacks of cement at 345 ft -  
Mud to 20 ft. Plug x 10 sacks of cement  
at the surface.

RECEIVED

Conservation Div.

MAY 26 1950

STATE CORPORATION  
COMMISSION  
KANSAS

05-26-50

District Conservation Agent G. H. Stover

Date 5-24-50

LF

**PLUGGING**  
FILE SEC 1 TWP 22 R 14W  
BOOK PAGE 8 LINE 5