

DISTRICT CONSERVATION AGENT'S REPORT

*[Handwritten signature]*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 34-31

LOCATION NW-NE-SW

SEC. 13 TWP. 22 RGE. 18-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 4 Lease M. Sittler - "D"

Operator Standard Oil & Gas Co Address Box #7, Ellinwood-Kans-

Field \_\_\_\_\_ County Stafford

Total Depth 3635 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 1/8 - 640 ft Circulated with cement  
5/8 casing set at 3631 ft. Cemented with 150 sacks cement  
Plugged back to 3620 ft with shot - Dumped 50 sacks of  
cement at 3620 ft - Shot off & pulled the 5/8 casing  
Filled with mud to 250 ft - Set Rock Bridge & 25 sacks  
of cement at 250 ft - Mud to 30 ft - Bridge &  
10 sacks of cement at the surface -  
Pipe Pulling Inc. Plugging contractor*

RECEIVED  
STATE CORPORATION COMMISSION

OCT 28 1950 10-28-50

CONSERVATION DIVISION

District Conservation Agent *[Signature]*

Date 10-26-50

**PLUGGING**  
FILE SEC 3 T 22 R 18W  
BOOK PAGE 34 LINE 31