

Form CP-3
Rev. 6-26-62

K
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 4 1965

2-4-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pan American Petroleum Corporation

Complete Address: Box 432, Liberal, Kansas

Lease Name Max Sittner "D" Well No. # 5

Location NE NE SW Sec. 3 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3747'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Murfin Drilling Company

Address: 617 Union Center, Wichita, Kansas License No. _____

Operation Completed: Hour 3:30PM Day 3rd Month Feb. Year 1965

The Above well was plugged as follows:

728' of 8 5/8" surface pipe, cement circulated with 500 sacks. Fluid level in the hole was at 155'. 1st cementing plug and 1/4 sack of hulls was pushed in fluid to 250', and cemented with 25 sacks, through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged solid with hulls and dry cement on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/4/65

INV. NO. 639-4