

15.185-01979-0001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION *R*

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 7 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pan American Petroleum Corporation

Complete Address: P. O. Box 432, Liberal, Kansas

Lease Name M. Sittner "D" Well No. # 2

Location NE SW SW Sec. 3 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3635'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 10:15AM Day 4th Month Feb. Year 1966

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cemented with 175 sacks. 3630' of 5 1/2" long string, cemented with 75 sacks. Plug back to 3580'. Top perferation 3319'.
Bottom plug was pushed to 3300', 50' of sand, and cemented with 5 sacks, through the dump bailer. 1809' of 5 1/2" long string was recovered from the hole. Fluid was up in the hole. Bridge plug was pushed in fluid to 248', rock bridge from 248' to 240'. 5 sacks of cement was mixed in barrel, and put on plug at 240', through the dump bailer, and let set over-night. Next morning hole was bailed dry, and hole was filled with 3 1/2 yards of ready-mix cement, from 225' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/8/66
INV. NO. 2901-U