



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

3-21-75

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1975

Operator's Full Name H.A. Chapman Investments CONSERVATION DIVISION
Wichita, Kansas

Complete Address Box 65 Great Bend, KS

Lease Name Sittner A Well No. 1

Location SW/SE/NW Sec. 4 Twp. 22 Rge. 12 (E) (W)

County Stafford Total Depth 3641

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 11:30 AM Day 20 Month 3 Year 1975

The above well was plugged as follows:

238 ft 8 5/8 surface cemented with 260 sacks. 3538 ft 5 1/2 long string
cemented with 100 sacks. Top perf. 3312 ft. Sand to 3300 ft, 5 sacks
cement with bailer. Pulled 2827 ft 5 1/2. Pump 3 sacks hulls, 20 sacks
gel, 100 sacks cement to surface.

Pumped by Halliburton Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 3/26/75

INV. NO. 1045-W