

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,850-0000

NE SW NE, Sec. 4, T 22 S, R 12 W

1650 feet from N/E section line

1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6393

Lease Name Stargel Well # 3

Operator: Brougher Oil Inc
Name & Address: P.O. Drawer 1367
Great Bend, KS 67530

County Stafford

Well Total Depth 3730 feet \$121.23

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 316

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Mohawk Drilling Inc License Number 6394

Address P.O. Box 1362 Great Bend, KS 67530

Company to plug at: Hour: 1:00 pm Day: 21 Month: September Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Terry Williams

(company name) Mohawk Drilling Inc (phone) _____

were: To use 60/40 pozmix 2% gel 3% cc

1st plug @ 3700' w/25sx, 2nd plug @ 570'
w/50sx, 3rd plug @ 330' w/40sx, 4th plug
@ 40' w/10sx + solid Bridge plug. Circulate
10sx in Rathole circulate 10sx in Mousehole

Signed Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5:45 pm Day: 21 Month: September Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered in above paragraph
Halliburton pumped the cement

RECEIVED
STATE CORPORATION COMMISSION

SEP 28 1983

CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

INVOICED

DATE 10-4-83

INV. NO. 5626-W

Signed Richard W. Lacey
(TECHNICIAN)