

15-185-12267-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD Strike out upper line when reporting plugging of formations.

Stafford County, Sec. 35 Twp. 23 Rge. 12 (E) (W)  
Location as "NE1/4NW1/4SW1/4" or footage from lines SE NE SW



Locate well correctly on above Section Flat

Lease Owner M. B. Armer et al  
Lease Name Kelly Well No. B 1  
Office Address 306 Insurance Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed August 23 1949  
Application for plugging filed August 23 1949  
Application for plugging approved August 23 1949  
Plugging commenced August 23 1949  
Plugging completed August 23 1949  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes  
Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation dry Depth to top Bottom Total Depth of Well 3927 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Kansas City	dry	3393				
Arbuckle	dry	3890	3927	8-5/8"	162'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud from 3927 ft. up to 162 ft. Set plug and dumped 15 sacks cement @ 162 ft. Mudded up to 30 ft. set plug and 10 sacks cement at surface

RECEIVED

AUG 27 1949

8-27-49

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to M. B. Armer  
Address 306 Insurance Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

M. B. Armer (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. B. Armer

306 Insurance Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 26th day of August, 1949

Hazel Watson Notary Public

My commission expires Sept. 17, 1951

My commission expires

PLUGGING  
FILE SEC 35 T 23 R 124  
BOOK PAGE 11 LINE 6

LOG

Owner: M. B. Armer et al  
Contractor: Armer Drilling Company, Inc.  
Drilling Commenced: 8/4/49  
Drilling Completed: 8/23/49  
Elevation: 1851 U. S.  
(Rotary Rig #2)

Farm: Kelly - well #B1  
Location: SE 1/4 6E Sec. 35-23-12,  
Stafford County, Kansas  
Casing record: 8-5/8" set @ 162'  
with 175 sacks cement

(figures below indicate bottoms)

Sand	130
Blue shale	162
Red bed	220
Red bed & sand	630
Anhydrite	690
Shale	705
Shale & shells	1615
Shale & sandy lime	1705
Port Riley lime	1770
Lime & shale	1960
Lime	2010
Lime & shale	2085
Shale & shells	2320
Shale	2410
Shale & shells	2525
Shale & lime	2625
Lime & shale	2825
Shale & shells	2955
Shale & lime	3025
Lime	3150
Shale & lime	3210
Lime	3290
Lime & shale	3370
Shale	3380
Lime	3437
Lime, soft	3497
Cherty lime	3515
Lime, hard	3555
Lime	3610
Lime & shale	3630
Shale	3679
Shale & chert	3716
Lime & chert	3742
Lime	3766
Lime & chert	3779
Lime & shale	3794
Cherty lime	3807
Lime & shale	3813
Lime	3840
Shale, lime & sand	3878
Shale & sand	3892
Lime	3927
Total Depth - rotary	3927 - D & A

ROPS:

Heebner shale	3215
Lansing-Kansas City	3393
Viola	3717
Simpson	3830
Artuckle	3890

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER DRILLING COMPANY, INC.

By *M. B. Armer*

STATE OF KANSAS }  
COUNTY OF STAFFORD } SO  
My commission expires Sept. 17, 1951 }

PLUGGING  
WELL SEP 23 1949  
BOOK PAGE 111 - LINE 6

Subscribed and sworn to before me, a notary public, in and for said County and State this 25th day of August, 1949.