

15-195-00527-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 35 Twp. 23 Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW SW SE  
Lease Owner The El Dorado Refining Company  
Lease Name Kelly Well No. 1  
Office Address Box 209 - Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-26 19 54  
Application for plugging filed 6-1- 19 54  
Application for plugging approved 6-2- 19 54  
Plugging commenced 6-3 19 54  
Plugging completed 6-7 19 54  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250'	
				5 1/2"	3866'	3290'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with sand from 3530' to 3475'

Run 5 sacks of cement at 3475'

Mudded to 250'

Set 10' rock bridge at 250'

Run 20 sacks of cement at 240'

Mudded to 35'

Run 10 sacks of cement at cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C. E. Shull Casing Pulling Company  
Address Box 558 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
Levi B. Sherman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Levi B. Sherman  
Box 209 - Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of June, 19 54

My commission expires 11-14-56

Vessel J. Frank  
Notary Public.

PLUGGING  
FILE SEC 35 T 23 R 12W  
BOOK PAGE 38 LINE 25

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 17 1954  
CONSERVATION DIVISION  
Wichita, Kansas

15-185-00522-0000

WELL LOG ----- -KELLY # 1

Located: NW SW SE Sec. 35-23-12  
Stafford County, Kansas.

OWNER: El Dorado Refining Company  
ROTARY DRILLING CONTRACTOR: Group Exploration Company  
CABLE TOOL CONTRACTOR:

Commenced: 5-3-54 (w.r.)  
(w.c.t.)

Completed: 5-17-54 (w.r.)  
(w.c.t.)

Total Depth: 3869'

LOG

CASING RECORD

0- 120	Sand
120- 625	Anhydrite
650-1350	Shale & Shells
1350-1550	Lime & Shale
1550-1825	Lime
1825-2680	Lime & Shale
2680-2775	Lime
2775-2915	Lime & Shale
2915-3295	Lime
3295-3375	Shale
3375-3800	Lime
3800-3868	Shale & Lime
3868-3869	Lime

Ran 250' of 8 5/8" casing,  
cemented with 175 sacks of  
cement.

Ran or set at 3866' 5 1/2"  
casing, cemented with 100  
sacks of cement.

PRODUCTION

**PLUGGING**  
 FILE SEC 35-23-12  
 BOOK PAGE 38 LINE 25

CONSERVATION DIVISION  
Wichita, Kansas