

Owner --- W. N. Bartlett
Contractor --- E. K. Carey, Contractor

S $\frac{1}{4}$ of the SE $\frac{1}{4}$ of the SE $\frac{1}{4}$ Sec. 36-23-12
Stafford County, Kansas

Date Commenced --- 7/16/43
Date Completed --- 9/3/43

15485-12396-0000

KELLY #1

FROM	TO	
0	25	Soil & shale
25	180	Sand
180	250	Red bed
250	265	Sand
265	630	Red rock (8 5/8" O. D. Casing, Cemented at 297' -- 150 sacks by Halliburton with 200 pounds calcium-chloride
630	655	Anhydrite
655	930	Shale & shells
930	1150	Shale
1150	1225	Salt
1225	1575	Lime & shale
1575	1730	Lime
1730	1890	Lime & shale
1890	1905	Sandy lime
1905	1930	Lime & shale
1930	1960	Sandy lime
1960	2180	Lime
2180	2320	Shale & lime
2320	2340	Sandy lime
2340	2455	Lime & shale
2455	2505	Shale
2505	2535	Lime
2535	2590	Shale
2590	2612	Lime
2612	2696	Lime & shale
2696	2766	Shale & shells
2766	2930	Shale & lime
2930	3243	Lime
3243	3271	Shale & shells
3271	3310	Shale
3310	3420	Shale & shells
3420	3470	Lime
3470	3528	Lime & broken
3528	3535	Lime hard
3535	3656	Lime
3656	3755	Shale & shells
3755	3763	Lime (Coring)
3763	3777	Shale & shells
3777	3818	Cherty Lime
3818	3869	Lime
3869	3917	Shale
3917	3924	Sand
3924	3929	Coring
3929	3959	Lime (Arbuckle)

DEC 18 1947

Dry and Abandoned

Casing Record

Ran 128 joints, 5 $\frac{1}{2}$ OD 17 pound new 8-rd. thd. casing. Cemented 75 sacks regular cement. Perforated Lane Well 3762 to 3766. Acidized.

I hereby certify that the above is a true and correct log of the above described well.

(Signed) E. K. Carey

PLUGGING			
FILE	SEC	23	R
BOOK	PAGE	94	LINE 33