

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-20217 0000

LEASE NAME Ragsdale

WELL NUMBER #1

1170' Ft. from S Section Line

2640' Ft. from E Section Line

SEC. 16 TWP. 21 RGE 32 (E) or (W)

COUNT Finney

Date Well Completed 5/27/76

Plugging Commenced 12/27/00

Plugging Completed 12/27/00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Benchmark Oil & Gas Corporation

ADDRESS 1515 Arapahoe Street, Suite 580 Denver, CO 80202

PHONE # (303) 592-9251 OPERATORS LICENSE NO. 31566

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/27/2000 (date)

by Kevin Strube KCC-Dodge City, KS (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? No data received from previous operator.

Producing Formation Chase Depth to Top 2679' Bottom 2689' T.D. 2723'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

JAN 08 2001

CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Pulled rods, pump and tubing. Ran tubing back into well to 2656' and spotted 200#'s of hulls. Pulled tubing up to 2390' and spotted 20 sks of 60/40 pos cement w/6% gel mixed with 100 pounds of hulls. Pulled tubing up to 1358' and pumped 65 sks of cement down tubing and circulated fluid to surface. Pulled tubing from well and pumped 80 sks of cement down 4 1/2" casing at 1300#'s pressure. Hooked onto the surface casing and pumped 175 sks of cement down the surface casing. ISIP 300#'s. Topped the 4 1/2" casing off with 10 sks of cement. TOTAL CEMENT USED 350 SKS. With 300 pounds of hulls.

Name of Plugging Contractor Benchmark Oil and Gas Corporation License No. 31566

Address 1515 Arapahoe Street, Suite 580 Denver, CO 80202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Benchmark Oil and Gas Corporation

STATE OF Colorado COUNTY OF Denver, ss.

Cindy A. Tokarchik Production Coordinator (Employee of Operator) or (Operator) or

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Cindy A. Tokarchik

(Address 1515 Arapahoe St., Suite 580 Denver, CO 80202)

SUBSCRIBED AND SWORN TO before me this 3 day of January, 20 01

Manda M. Stuenkel
Notary Public

My Commission Expires: 03/11/2002

Form CP-4
Revised 05-88

