

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,695-0000

LEASE NAME Erich Fruehauf

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 15 TWP. 22 RGE. 12 (E) or (W)

COUNTY Stafford

LEASE OPERATOR JFW, Inc.

ADDRESS RR 1 Box 26 Plevna, KS 67568-9718

PHONE#(316) 286-5318 OPERATORS LICENSE NO. 9324

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 08-08-90

Plugging Commenced 08-08-90

Plugging Completed 08-08-90

The plugging proposal was approved on 08-07-90 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? to be filed by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3730

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Bottom Plug: @ 3679' w/40 sacks cement thru drill pipe

Next Plug: @ 680' w/50 " " " " " " 15 sacks in Rat Hole

Next Plug: @ 250' w/40 " " " " " " Water well filled w/cement

Top Plug: @ 30' w/10 " " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: JFW, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson


(Employee of Operator) or ~~Contractor~~

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

8-21-90

(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530



RECEIVED
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 20th day of AUGUST, 19 90

Sally R. Byers
Notary Public

My Commission Expires: DECEMBER 10, 1992
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S WELL LOG

DATE COMMENCED: August 2, 1990
DATE COMPLETED: August 8, 1990

JFW, Inc.
ERICH FRUEHAUF #1
SE SE SW
Sec. 15, T22S, R12W
Stafford County, Ks.

0 - 635' Surface Soil, Red Bed
635 - 658' Anhydrite
658 - 1417' Shale
1417 - 2856' Shale & Lime
2856 - 3153' Lime
3153 - 3172' Shale & Lime
3172 - 3186' Lime
3186 - 3283' Shale
3283 - 3396' Lime & Shale
3396 - 3556' Lime
3556 - 3613' Chert
3613 - 3681' Shale & Snad
3681 - 3730' Dolomite
3730' RTD

ELEVATION: 1860 K.B.


Surface Pipe: Set new
8-5/8", 20# pipe @226'
w/150 sacks 60/40 pozmix
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 20th day of August 1990:



RECEIVED
STATE COMMISSION

CONSERVATION DIVISION
Wichita, Kansas