

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 15 TWP. 22S RGE. 12W E/W
Location as in quarters or footage from lines:
C 3/2 NE 1/4

Lease Owner Clark T. Snider Living Trust
Lease Name Messery #1 Well No.
Office Address 4519 E. English Wichita, Kansas 67218
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed
Application for plugging filed
Plugging commenced 4-21-82
Plugging completed 4-27-82
Reason for abandonment of well or producing formation

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz
Producing formation Depth to top bottom T.D. 3672'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	257'	none
				5-1/2"	3660'	2832'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from feet
to feet for each plug set.

Plugged off bottom with sand to 3600' and ran 5 sacks cement. Shot casing @3116',
2995' and 2847'. Pulled a total of 88 joints of 5-1/2" casing. Plugged well with
5 sacks bulls, 25 sacks gel, 8-5/8" plug, 140 sacks 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

5-13-82
STATE CORPORATION COMMISSION
RECEIVED
MAY 13 1982
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of April, 19 82

My Commission expires:  IRENE HOOVER
State of Kansas
My Comm. Exp. Aug. 15, 1985

Irene Hoover
Notary Public.



Shields


15-185-30258-0000

Russell, Kansas

WELL LOG

Operator: T. O. Gaskill
 Well: Messerly #3
 Commenced: December 13, 1965
 Completed: December 20, 1965
 Contractor: Shields Drilling Co., Inc.

Well Description: C W/2 NE/4
 Sec. 15-22S-12W
 Stafford Co., Kansas



Elevation: 1858 KB 1853 gr. 1.
 Treatment: 200 gals. acid

Production: Swabbed 9BFPH -25% water

CASING RECORD

Size	Run	Pulled
8 5/8"	257'	Cmtd w/ 250 sax
5 1/2"	3,660'	Cmtd w/ 75 sax

Tops:

Anhydrite	640'
Topeka	2850'
Heebner	3146'
Toronto	3166'
Brown Line	3277'
Lans. KC	3293'
Base KC	3520'
Viola	3551'
Simpson sh.	3598'
Arbuckle	3659'
Total D.	3672'

..... Figures Indicate Bottom of Formations

Sand & Clay	120'
Sand & Shale	258'
Redbed & Shale	641'
Anhydrite	661'
Shale, Shells & Salt	1,195'
Shale & Shells	1,550'
Lime & Shale	3,020'
Lime	3,672' RTD

RECEIVED
 STATE OF KANSAS

MAR 22 1967

CONSERVATION BOARD
 Topeka, Kansas

Notes