


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County. Sec. 15 Twp. 22 Rge. 12 (E) (W) X  
Location as "NE/CNW4SW4" or footage from lines C SW NW  
Lease Owner Icer Addis  
Lease Name Spangenburg Well No. 1  
Office Address Box 519, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D. & A.  
Date well completed October 25 1962  
Application for plugging filed October 25 1962  
Application for plugging approved October 25 1962  
Plugging commenced October 25 1962  
Plugging completed October 25 1962  
Reason for abandonment of well or producing formation -0-



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production -0- 19      
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. J. J. J. J.  
Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 3685' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	257'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Rotary mud was used to fill up hole to a depth of 160' where 1st plug was set using 1/4 sack hulls and 25 sacks cement, filling up hole to a depth of 40' where 2nd plug was set using 1/4 sack hulls and 10 sacks cement and filling hole to top.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 6 1962  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor L. J. DREILING AND SONS, INC.  
Address VICTORIA, KANSAS

STATE OF Kansas, COUNTY OF Barton, ss.  
I, Leo F. Dreiling the contractor ~~an employee of owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling  
(Address)     

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 1962  
Jessie Lee Sum  
Notary Public.

My commission expires July 1, 1964



L. J. DREILING and SONS, Inc.  
VICTORIA, KANSAS

WELL LOG

Company Icer Addis  
Box 519, Great Bend, Kansas  
Farm Spangenburg No. 1

Sec. 15 Twp. 22 Rng. 12  
Location C SW NW  
County Stafford County, Kansas

Total Depth 3685'

Comm. 10-18-62 Comp. 10-25-62

Elevation: D. F.

Contractor L. J. DREILING AND SONS, INC.  
VICTORIA, KANSAS

G. R.

Casing Record Cement Record  
8 5/8" - - - - 257' 250 sacks cement

Production:  
D. & A.

Figures Indicate Bottom of Formations

0 - 50	Surface Clay
50 - 257	Shale & Sand and Red Rock
257 - 640	Shale & Red Rock
640 - 670	Anhydrite
670 - 757	Shale
757 - 1572	Shale & Shells
1572 - 1800	Shale & Broken Lime
1800 - 2005	Shale & Lime
2005 - 2265	Lime & Shale
2265 - 2643	Shale & Lime
2643 - 2895	Lime & Shale
2895 - 3088	Shale & Lime
3088 - 3225	Lime
3225 - 3340	Lime
3340 - 3400	Lime
3400 - 3422	Lime
3422 - 3480	Lime
3480 - 3500	Lime
3500 - 3574	Lime
3574 - 3622	Lime
3622 - 3660	Lime & Shale
3660 - 3685	Lime
3685	TD

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 6 1962  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
COUNTY OF ELLIS ) ss.

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc.,  
upon oath states that the above and foregoing is a true and correct  
copy from the Daily Drilling Report on your Spangenburg No. 1.

Leo F. Dreiling  
Leo F. Dreiling

Subscribed and sworn to before me this 2nd day of November, 1962.

Ronald Zimmerman  
Notary Public

My Commission Expires: August 14, 1965