

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-20,217-00-02

LEASE NAME C. Curtis

WELL NUMBER 1-Y

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 15 TWP. 22S RGE. 12W (E) or (W)

LEASE OPERATOR Rupe Oil Company, Inc.

COUNTY Stafford

ADDRESS P.O. Box 783010 Wichita, Kansas 67278-3010

Date Well Completed

PHONE# (316) 689-3520 OPERATORS LICENSE NO. 5047

Plugging Commenced 6-6-01

Character of Well SWD

Plugging Completed 6-12-01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom 3665.5 T.D. 3665-1/2'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	251'	None
				5-1/2"	3656'	2600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plug used, state the character of same and depth placed, from feet to feet each side. Plugged off bottom with sand to 3200' and 5 sks. cement. Shot pipe @2600', pumped 300# hulls, 10 sks. gel, 50 sks. cement, 10 sks. gel and 100# hulls, released plug, pumped 100 sks. of cement. 60/40 pos, 6% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

RECEIVED
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rupe Oil Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss. JUL 9 2001

Mike Kelso

(Employee of Conservation Division)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 6th day of July ~~XXX~~ 2001

[Signature]
Notary Public

My Commission Expires:



OR