

**RECEIVED**

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

**AUG 22 2001**

LEASE OPERATOR KCC WICHITA  
Continental Energy

ADDRESS P O Box 918

PHONE# 620 27608710 OPERATORS LICENSE NO. 05317

Character of Well \_\_\_\_\_

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-01-01 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Chase Depth to Top 2682 Bottom 2719 T.D. 2740

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS CASING RECORD**

Formation	Content	From	To	Size	Put In	Pulled out
Chase	Gas	Surface	2759	4 1/2"	2759	None
		Surface	350	7"	350	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set  
Pump 70 sks 60-40 Poz Mix 6% Gel 300# Halls thru tubing @ 2600'  
Perf 1350' Pump 100 sks @ 1500' thru tubing  
Pump 10 sks down 4 1/2" max pressure 1300# Pump 130 sks down 7" max pressure 700#  
Shut in @ 300#

Name of Plugging Contractor Allied Cementing Co License No. N/A

Address P O Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Continental Energy

STATE OF KS COUNTY OF Finney, ss.


Russell Freeman (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Russell Freeman

(Address) Box 918 Garden City, KS 67846

SUBSCRIBED AND SWORN TO before me this 21 day of Aug, 2001

Karen Bogner  
 Notary Public



Expires: 10/11/04

OK