

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION Sec NW

SEC. 19TWP.22SRGE.31W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease N./Appleman/Op. Trekell

Operator N. Appleman Co. Address 665 Fifth Avenue,
New York 22, N. Y.

Field _____ County Finney

Total Depth 2772 Feet.

Plugging Contractor Gibson Machine & Tool Co.,

Plugging Contractor's License No. 268

Address Box 1111, Borger, Texas

(Describe briefly the manner in which the well was plugged)

Mudded hole up to 371 feet. Set bridging plug at 371 feet and

ran 30 sacks of cement from 371 feet to 279 feet. Bridging plug

at 279 feet. Filled with mud to 50 feet. Ran 20 sacks of

cement to 4 feet under surface. Cut off 8-5/8" 4 feet below

surface and welded plate on top.

2-10-55

RECEIVED
STATE CONSERVATION DIVISION

R. J. Phillips
District Conservation Agent

FEB 10 1955

CONSERVATION DIVISION
Wichita, Kansas

DATE January 15, 1955

PLUGGING
FILE SEC 19 T 22 R 31W
BOOK PAGE 82 LINE 12