

J.P.
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 1965

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Jetmar Production Company

Complete Address: Box 736, Great Bend, Kansas

Lease Name Mershon Well No. # 1

Location SE SE SW Sec. 24 Twp. 22 Rge. 12 (E) (W)W

County Stafford Total Depth 3656'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Apex Casing Pulling Company, Inc.

Address: 739 E. Second, Hoisington, Kansas License No. 544

Operation Completed: Hour 12:30PM Day 1st Month Nov. Year 1965

The Above well was plugged as follows:

256' of 8 5/8" surface pipe, cemented with 200 sacks. 3653' of 4 1/2" long string,
cemented with 125 sacks. Plug back to 3395'. Top perferation 3315'. Bottom of
the hole was sanded to 3300', and cemented with 3 sacks. 2837' of 4 1/2" long
string was recovered from the hole. Fluid was up in the hole. Bridge plug was
pushed in fluid to 240', rock bridge from 240' to 230'. 6 sacks of cement was
mixed in a barrel, and put on plug at 230', through the dump bailer, and let
set over-night. Next morning hole was bailed dry, and 19 sacks of cement was
added to the plug. Hole was filled with mud to 40', rock bridge from 40' to
30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/3/65

INV. NO. 2110-W

Signed: Archie Elving
Well Plugging Supervisor