

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. R

LOCATION C.N.W. 1/4

SEC. 24 TWP. 22 RGE. 12W

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Heyer

Operator H.O. Herrfeldt Address Wichita, Kan 315 Derby Bldg

Field - County Stafford

Total Depth 3657 Feet.

(Describe briefly the manner in which the well was plugged)

The hole was cemented 3657 ft to 3600 ft
5 sac. heavy mud. 3600 ft to 225 ft. cement
225 ft to 180 ft 10 sac. mud. 180 ft to 15 ft
Cement into base of cellar 10 sac
237 ft of 8 3/8 pipe cemented & left in the hole

5-10-47

A. W. Kern
District Conservation Agent

Date 5-5-47

PLUGGING
FILE SEC 24 T 22 R 12W
BOOK PAGE 109 LINE 20

MAY 19 1947

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - STURM & HERSHFIELD
Farm - C. Heyen No. 1.

SEC. 24 T. 22 R. 12 W
C NW NW

DISCOVERY WELL

Total Depth. 3657'
Comm. 9-29-43 Comp. 11-11-43
Shot or Treated.
Contractor. Creekmore Drlg. Co.
Issued. 4-22-44

County. Stafford
KANSAS



CASING:
8" 234'
5" 3649'

Elevation. _____

Production. Pot. 75 B. Est.

Figures Indicate Bottom of Formations.

sand	0-62
red rock & shales	225
shell & red rock	608
anhydrite	640
shale & shells	1515
lime	1590
shale & lime shells	1620
lime brkn	1700
lime	1840
lime brkn	2325
lime brkn & shale	2900
shale	2905
lime	3150
shale	3213
lime	3220
shale	3295
shale & lime	3315
lime brkn	3350
lime	3425
shale	3440
shale & lime shells	3463
lime brkn	3520
lime	3548
shale	3562
lime cherty	3596
shale	3655
lime	3657
Total Depth.	

Complete 8-25-47

PLUGGING
FILE SEC 24 T 22 R 12 W
BOOK PAGE 109 LINE 20