

10 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Jetmar Production Company

Complete Address: Box 736, Great Bend, Kansas

Lease Name Mershon Well No. # 2

Location SW SE SW Sec. 24 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3770'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated: _____

Plugging Contractor: Apex Casing Pulling Company

Address: 739 E. Second, Hoisington, Kansas License No. 544

Operation Completed: Hour 11:15AM Day 6th Month Nov. Year 1965

The Above well was plugged as follows:

255' of 8 5/8" surface pipe, cemented with 200 sacks. 3716' of 5 1/2" long
string, cemented with 125 sacks. Top perforation 3350'. Bottom plug was
pushed to 3400', and 60' of sand, and cemented with 5 sacks. 2737' of 5 1/2"
long string was recovered from the hole. Fluid was up in the hole. Bridge
plug was pushed in fluid to 240', rock bridge from 240' to 230'. 5 sacks
of cement was mixed in barrel and put on plug, through dump bailer, and
let set over-night. Next morning hole was bailed dry, and 20 sacks of
cement was added to the plug. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 11/9/65
INV. NO. 2148-W