

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 189-17

LOCATION C-SE 21W

SEC. 14 TWP. 22 RGE. 12-w

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Neuman

Operator The Lotus Oil Co Address 900 Land Bldg. N. City - Mo.

Field _____ County Stafford

Total Depth 3642 Feet.

(Describe briefly the manner in which the well was plugged)

Sweep pipe 10 3/4 - 232 ft. Circulated with cement
5/8 casing set at 3632 ft. 150 sacks of cement. Plugged
back to 3630 ft. with chat. Mixed 5 sacks of cement
at 3630 ft. tipped off & pulled the 5/8 casing - mud
to 232 ft. Set Rock Bridge & 20 sacks of cement
at 232 ft. mud to 35 ft. Plug & 10 sacks of
cement at the surface.

Jack Walker - Plugging Contractor

STATE CORPORATION COMMISSION
JAN 29 1952

C. M. Stough
District Conservation Agent

Date 1-26-52

PLUGGING
FILE SEC 24 T 22 R 17
189-17-17

CONSERVATION DIVISION
Wichita, Kansas