

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENCY'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-055-20238-0000 (of this well)

Operator's Full Name Mack Oil Company

Complete Address 908 Union Center, Wichita, Kansas 67202

Lease Name Foster Well No. 1

Location C NE SE Sec. 31 Twp. 22 Rge. (E) (W) 30

County Finney Total Depth 4950'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 2 P Day 13 Month 1 Year 1978

The above well was plugged as follows:

RECEIVED
STATE CORPORATION COMMISSION

Total Depth 4950' 8 5/8 csg set 373' cwc 250 sk.

4 1/2 csg set 3170' cw 225 sk cem.

JAN 16 1978

1-16-78

4 1/2 csg PBTB 3149' with perf. (2694'-2704')

CONSERVATION DIVISION
Wichita, Kansas

Pumped down 4 1/2 csg with 100 lbs hulls & 35 sk cem. Top of cement 2400'.

Cutoff & recovered 2337' of 4 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel w/100 lbs

hulls -followed with 70 sk cem. -displaced with 8 sk gel & water -& capped with

cementing plug & 80 sk cem. FPP 500 lbs. Cementing Material "Halliburton-Light"

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Messer
Well Plugging Supervisor

DATE 1-17-78

6580-W