

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202Intent to Drill,
filed December 5, 1967.RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1967

12-20-67
CONSERVATION DIVISION
WICHITA, KANSASOperator's Full Name Petroleum, Inc.Complete Address: 300 West Douglas, Wichita, Kansas 67202Lease Name Simpson "E" Well No. # 2Location SW SW NW Sec. 10 Twp. 21 Rge. 13 (E) (W) WCounty Stafford Total Depth 3610'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Garvey Drilling CompanyAddress: R. R. # 2, Great Bend, Kansas 67530 License No. Operation Completed: Hour 9:00PM Day 17th Month December Year 1967

The Above well was plugged as follows:

290' of 8 5/8" surface pipe, cement circulated with 350 sacks. Fluid level
in the hole was at 85'. 1st cementing plug and 1/2 sack of hulls was pushed in
fluid to 275', and cemented with 25 sacks, through the drill pipe, with cement
from 275' to 200'. Hole was filled with drilling mud to 40', 2nd cementing plug
bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and
cemented with 9 sacks, with cement from 30' to the base of the cellar. Rat and
mouse holes bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 12/20/67INV. NO. 6944-u