

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 124-44

LOCATION NE-SW-NE

SEC. 10 TWP. 21 RGE. 13-ew

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3 Lease Cuvalt

Operator Westgate-Greensand Oil Co. Address 2009 Central Bldg. Wichita-Kans.

Field \_\_\_\_\_ County Stafford

Total Depth 3560 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 254 ft - Circulated with cement  
5 1/2 casing set at 3533 ft - 75 sacks of cement - Plugged  
back to 3540 ft with chat - Dumped 5 sacks of  
cement at 3540 ft - Ripped off & killed the 5 1/2 casing -  
run to 254 ft - Set Rock Bridges & 15 sacks  
of cement at 254 ft. run to 35 ft - Bridge &  
15 sacks of cement at the surface.  
Morgan Well Plugging Service - Plugging Contractor

JAN - 2 1952

1-2-52

DISTRICT CONSERVATION AGENT  
C. H. Stouck  
District Conservation Agent

PLUGGING  
FILE SEC 10 T 21 R 13W  
BOOK PAGE 124 LINES 44

Date 12-29-51