

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-21,938-0000 Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR RAMA Operating Co., Inc. KCC LICENSE # 3911 9/94
(owner/company name) (operator's)

ADDRESS P. O. Box 159 CITY Stafford

STATE Kansas ZIP CODE 67578 CONTACT PHONE # (316) 234-5191

LEASE Ochel WELL# 1 SEC. 15 T. 22 R. 13W (East/West)

- NE - SE - SW SPOT LOCATION/QQQQ COUNTY Stafford

 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# 2-3-94

CONDUCTOR CASING SIZE SET AT CEMENTED WITH RECEIVED SACKS

SURFACE CASING SIZE 8 5/8 SET AT 328' CEMENTED WITH STATE CORPORATION COMMISSION SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3869' CEMENTED WITH FEB - 5 1994 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs 3830-32 CONSERVATION DIVISION
Wichita, Kansas

ELEVATION 1890/1895 T.D. 3870' PSTD ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING According to the rules and regulations of the
State of Kansas.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED?

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Robert Austin PHONE# () 316-234-5191

ADDRESS P. O. Box 159 City/State Stafford, KS 67578

PLUGGING CONTRACTOR Kelso Casing Pulling, Inc. KCC LICENSE # 6050 9/94

ADDRESS P. O. Box 347 Chase, KS 67524 PHONE # (316) 938-2943

PROPOSED DATE AND HOUR OF PLUGGING (If known?) ASAP

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1-28-94 AUTHORIZED OPERATOR/AGENT: P. Austin
(signature)

15-185-21938-0000

EURAM PETROLEUM, INC.

15-22-13W

BOX 272

#1 OCHEI

NE SE SW

RUSSELL, KS 67665

CONTR

REVLIN DRILLING, INC.


CTY

STAFFORD

GEOL

FIELD

KENILWORTH



ELV

1895 KB

SPD

1/27/84

CARD

ISSUED 7/19/84

IP

P 25 80 & 140 BWPD

1890 GL

ARB 3830-3832

LOG	Tops	Depth-Datum
HEEB	3244-1349
TOR	3267-1372
DOUG	3281-1386
BR LM	3377-1482
LANS	3397-1502
BKC	3621-1726
CONG	3673-1778
VIOLA	3694-1799
SIMP SD	3749-1854
ARB	3796-1901
RTD	3870-1975

API 15-185-21,938

8 5/8 " 328 / 225SX, 5 1/2 " 3869 / 150SX

DST (1) 3513-3535 (LANS) / 30-30-30-30, REC 10' SL OIL SPKD M, SIP 72-61#, FP 48-48 / 53-61#

DST (2) 3538-3600 (LANS) / MISRUN

DST (3) 3702-3752 (VIOLA, SIMP) / 45-30-30-30, REC 30' M, SIP 62-69#, FP 50-50 / 59-69#

DST (4) 3730-3801 (SIMP, ARB) / 30-30-30-30, REC 30' SL OIL SPKD M, W / SCUM OIL, SIP 888-829#, FP 46-46 / 91-54#

DST (5) 3733-3803 (SIMP, ARB) / MISRUN

DST (6) 3734-3804 (SIMP, ARB) / 30-30-30-30, REC 65' M, SIP 853-881#, FP 42-42 / 72-62#

MICT - CO, PF (ARB) 3830-3832, W/2 SPF, SWB DRY, ONFU 300' FL (50% OIL), AC 250G (15% INS), SWB DWN, FU 1000' FL (15% OIL), POP, P 25 80 & 140 BWPD, (GR 20"), 5/9/84

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

NOTE: CORRECTION 3/29/84 ~ ORIGINALLY FIRST REPORTED AS RUTHVEN, INC., AS OPERATOR



Kansas Corporation Commission

Joan Finney, Governor Jim Robinson, Chairman F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

February 3, 1994

Rama Operating Co Inc
P O Box 159
Stafford KS 67578

Ochel #1
API 15-185-21,938-0000
NE SE SW
Sec. 15-22S-13W
Stafford County

Dear Robert Austin,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760