

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 312 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-185-30263-0000

RECEIVED  
STATE CORPORATION COMMISSION

JUL 7 1966

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

CONSERVATION DIVISION  
WICHITA, KANSAS

7-7-66

Dear Sir:

Mr. Olin Kelso of Sterling Drilling Company as this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: Box 127, Sterling, Kansas

Lease Name: Gray Well No. # 4

Location: SE SW SW Sec. 18 Twp. 23 Rge. 13 (E)(W) W

County Stafford Total Depth 3680' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Kelso was instructed to plug the well as follows:

379' of 7" surface pipe, cement circulated with 160 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent